



AUGUST 31, 2022

CONTRACT NO. 1760 G, E, H, P

CSO BYPASS AND DISINFECTION

ADDENDUM NO. 6

All bidders bidding Contract No. 1760 G, E, H, P shall read and take note of this Addendum No. 6. The Contract Documents for Contract No. 1760 G, E, H, P – CSO Bypass and Disinfection are hereby revised and/or clarified as stated below.

Acknowledgement of Contract No. 1760 G, E, H, P ; Addendum No. 6

The Acknowledgement attached to Addendum No. 6 is to be signed and returned immediately via email to Kathleen P. Uniatowski at contract.clerks@alcosan.org and acknowledged with Bidder's Proposal.

Members of the Board

Sylvia C. Wilson
Chair Person

Shannah Tharp-Gilliam, Ph.D.
Harry Readshaw
Corey O'Connor
Jack Shea
Emily Kinkead
Paul Klein

Arletta Scott Williams
Executive Director

Douglas A. Jackson, P.E.
*Director
Operations & Maintenance*

Michelle M. Buys, P.E.
*Director
Environmental Compliance*

Kimberly N. Kennedy, P.E.
*Director
Engineering & Construction*

Karen Fantoni, CPA, CGMA
*Director
Finance*

Michael Lichte, P.E.
*Director
Regional Conveyance*

Jeanne K. Clark
*Director
Governmental Affairs*

Joseph Vallarian
*Director
Communications*

Julie Motley-Williams
*Director
Administration*


Kimberly Kennedy, P.E.
Director – Engineering and Construction

**ACKNOWLEDGEMENT OF
CONTRACT NO. 1760 G, E, H, P – CSO BYPASS AND DISINFECTION**

ADDENDUM NUMBER 6

FIRM NAME: _____

SIGNATURE: _____

TITLE: _____

DATE: _____

AUGUST 31, 2022

CONTRACT NO. 1760 G, E, H, P

CSO BYPASS AND DISINFECTION

ADDENDUM NO. 6



AUGUST 31, 2022

CONTRACT NO. 1760 G, E, H, P

CSO BYPASS AND DISINFECTION

ADDENDUM NO. 6

A. Contract Documents – Volume 1

1. N/A.

B. Contract Specifications – Volume 2

1. N/A.

C. Contract Specifications – Volume 3

1. N/A.

D. Contract Drawings

1. Replace drawing 840-S-14 with the attached.
2. Replace drawing 840-S-42 with the attached.
3. Replace drawing 840-S-44 with the attached.
4. Replace drawing 840-S-45 with the attached.

E. Questions

185. Question: Reference drawings 840-S-14, 840-S-42, & 840-S-45 : # 9s @ 6” o.c.e.w.t.&b. are indicated in section A / 840-S-42. # 7s @ 6” o.c.e.w. on top and # 7s @ 6” o.c. in one direction on the bottom and 12” o.c. in the other direction on the bottom are indicated in sections F & G / 840-S-45. Which one is correct ? What is the correct reinforcing to use for the base mat foundation detailed on these three referenced drawings?

Answer: For the base slab in the effluent and outfall area the reinforcing should be as follows: #7@6” Top Each Way; For the “short” direct reinforcing on the bottom should be #9@12” ALT W/ #10@12”; Reinforcing in the “long” direction on the bottom should be #9@6”. Refer to updated drawings attached.

186. Question: Reference drawings 840-S-14, 840-S-42, & 840-S-45 : The plan view on drawing 840-S-14 shows the new walls and mat foundation starting at the same point, approximately 80-feet from the north end of the structure. However, the section view on drawing 840-S-42 shows the new mat foundation ending just south of the second new interior wall, approximately 43-feet from the north end of the structure. Please confirm that the new mat foundation for the new north extension of the BCCT starts as the same location as the new walls, as indicated on the plan view.

Answer: Section is correct as indicated on 840-S-42. Refer to updated drawing.

Attachments:

Specifications:

- a. N/A

Drawings:

- a. 840-S-14
- b. 840-S-42
- c. 840-S-44
- d. 840-S-45

Other:

N/A

*** * * * END OF ADDENDUM NO. 6 * * * ***